BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of Work: Drilling of new borewell installation of motor, commissioning and laying of pipelines in ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
1	1.00	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.47, I. 9.4) PRED.SR 2012-13	Each	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Forty Six Paise Only
2	50.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,)Page no. 46 / I. 9.1 PRED SR 2012-13 0 to 50 m	M	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
3	50.00	50 to 100 m	M	412.00	Rupees Four Hundred Twelve Only
4	50.00	100 to 150 m	M	458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
5	50.00	150 to 200 m	M	484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
6	50.00	200 to 250 m	M	560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
7	50.00	251 to 300 m	M	600.49	Rupees Six Hundred and Forty Nine Paise Only
8	100.00	300 to 350 m	M	640.66	Rupees Six Hundred Forty and Sixty Six Paise Only
9	54.00	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) SE PRED III NO 84	Rmtr	1325.00	Rupees One Thousand Three Hundred Twenty Five Only

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
10	12	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 250mm dias. (Page No. 88 Item No. 12.116.5) PWD SR 2016-17	Rmtr	2175.12	Rupees Two Thousand One Hundred Seventy Five and Twelve Paise Only
11	1	Providing 175mm dia ms casing cap page no III it no 85 pred 12-13 sr	no	100.00	Rupees One Hundred Only
12	10	Providing MS Casing pipe collars page no III it no 86 pred 12-13 sr	no	150.00	Rupees One Hundred Fifty Only
13	1	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings. PAGE NO XXXXII	Unit	74300.00	Rupees Seventy Four Thousand Three Hundred Only
14	280	. KSRB13-3.1: Providing and fixing to wall celling and floor glavanised/ mild steel tubes (medium grade 1.27 kg /mt) B class 50 mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. (Page 90 ITEM NO 13.6)	Mtr	540.60	Rupees Five Hundred Forty and Sixty Paise Only
15	580	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and Powder coated extrued PVC sheathed suitable for working voltage upto 1100 Volts as per IS - 694 ; 1990 AND CONFORMING TO gtp OFGROUP A P. No. 12/ I No. (2.10.4) 3cx 6.0 Sqm KPWD Electrical SR 2014-15	Mtr	188.70	Rupees One Hundred Eighty Eight and Seventy Paise Only
16	50	Labour charges for erection of new/ repaired submersible pumpset along with gi pipes inculding transportion each length pno 558 ino 3 bwssb sr 14-15	No	88.00	Rupees Eighty Eight Only
17	1	Supplying and flush polished wood board with out front frount plank made of not less than 15mm thick plank after due groove cutting Finishing with necessary on fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44No.6.6.6 KPWD Electrical SR 2014-15	Each	302.00	Rupees Three Hundred Two Only
18	35	Supplying of 1.1 KV LT UG cable having aluminium condutor PVC insulated shethed, EXTREDED INNER SHEATHRD galvnised steel,stirp confirming IS 3975;1990 AND extruded PVC outer sheathing armoured cable IS 1554 part 1;1998 and confirming to GTP of group.P No.55/ I No.7.4.4 (4 core 16 Sqmm) KPWD Electrical SR 2014-15	Mtr	140.40	Rupees One Hundred Forty and Forty Paise Only
19	35	Labour charges for laying of 1.1 K.V class UG cable, P No. 61 / I No. 7.8.1 In existing trencg/duct 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15	Mtr	10.80	Rupees Ten and Eighty Paise Only
20	30	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., completeP No. 62/ I. No.7.9.4 KPWD Electrical SR 2014-15	Mtr	117.00	Rupees One Hundred Seventeen Only

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
21	3	Supplying and fixing of Class A (mealum duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 62/ I No.7.12.1 KPWD Electrical SR 2014-15	Mtr	345.00	Rupees Three Hundred Forty Five Only
22	1	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No.62/ I No. 7.13.2 KPWD Electrical SR 2014-15	No	280.00	Rupees Two Hundred Eighty Only
23	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, (P No.55, I No. 7.1) KPWD Electrical SR 2014-15	No	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
24	3	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No44/I No 6.7.4 KPWD Electrical SR 2014-15	Each	360.00	Rupees Three Hundred Sixty Only
25	6	Supplying and fixing of heavy duty glands for ug cable 1.1 kv etc., complete.... P No62 I No 7.14.2 KPWD Electrical SR 2014-15	Each	86.00	Rupees Eighty Six Only
26	1	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 32 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications pno 47 IT 6.16.5 KPWD Electrical SR 2014-15	Each	1547.00	Rupees One Thousand Five Hundred Forty Seven Only
27	200	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 P.No. 49, I. No.6.40.2 KPWD Electrical SR 2014-15	Sq.Cm	0.33	and Thirty Three Paise Only
28	1	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 Page No.90 Item No. 13.55 / PWD SR 2016-17	Nos	1585.76	Rupees One Thousand Five Hundred Eighty Five and Seventy Six Paise Only
29	2	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No.92/ I. No. 13.81.3 PWD SR	Nos	227.90	Rupees Two Hundred Twenty Seven and Ninety Paise Only
30	3	Gate value 50 mm nominal bore gun metal P. No.xxiii sl No. 673 PWD SR	Nos	1650.00	Rupees One Thousand Six Hundred Fifty Only

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
31	1	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. PRED Bangalore Circle SE Approved Date 30.07.2010 15HP to 30 HP Star Delta Starter	No	10000.00	Rupees Ten Thousand Only
32	72	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in ordinary soil, exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications.(P.No.5, I.No.2.1) PWD SR 2016-17	Cum	166.42	Rupees One Hundred Sixty Six and Forty Two Paise Only
33	14.4	KSRRB M2100-9. Sand Filling in Foundation Trenches as per Drawing & Technical SpecificationMORTH Specification No. 304. (P.No.217, I.No.27.17) PWD SR 2016-17	Cum	2922.42	Rupees Two Thousand Nine Hundred Twenty Two and Forty Two Paise Only
34	160	KSRB13-9.3 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 50mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.2 / 13.9 (Page no.94, Item No.13.73.1) PWD SR 2016-17	Rmtr	366.76	Rupees Three Hundred Sixty Six and Seventy Six Paise Only
35	57.6	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (Page No.6, Item No. 2.11) PWD SR 2016-17	Cum	80.56	Rupees Eighty and Fifty Six Paise Only
36	14.4	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications (Page No. 155, Item No. 20.18, PWD SR 2018-19)	Cum	2227.84	Rupees Two Thousand Two Hundred Twenty Seven and Eighty Four Paise Only
37	96	KSRRB 500-1.1 : Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No. 500-1.3 (Page No. 158, I. 21.1, PWDSR 2018-19)	Sqm	24.78	Rupees Twenty Four and Seventy Eight Paise Only

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
38	96	KSRRB M500-6: Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries complete as per specifications. MORTH specification NO. 502 (Page No. 158, Item No. 21.5, PWD SR 2018-19)	Sqm	51.92	Rupees Fifty One and Ninety Two Paise Only
39	3.84	KSRRB M500-18: Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 40-60 TPH capacity HMP with mechanical paver grading I (35-40mm) with 4.5% VG-30 Bitumen (Page No. 160, Item No. 21.20.5, PWD SR 2018-19)	Cum	8591.58	Rupees Eight Thousand Five Hundred Ninety One and Fifty Eight Paise Only

"NO OF CORRECTION NIL" "DTS APPROVED"

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))